

ATTACHMENT 2: ESTIMATED COSTS

Estimated quantities and associated cost based on lining one 3m x 3m x 1m washout:

36 sq. meters of 10 mil plastic x \$0.51 per sq. meter..... \$ 18.00

20 sandbags x \$3.00 per bag..... \$ 60.00

Sub-total estimated materials cost..... \$ 78.00

Mark ups at 15%..... 12.00

Total estimated materials cost..... 90.00

Labor

2 laborers x 1 hour @ \$50 per hour..... \$100.00

Total estimated Labor cost..... \$100.00

Mark ups at 17% and 33%..... 56.00

Total estimated labor cost..... 156.00

Total estimated cost for lining one 3m x 3m x 1m washout..... \$246.00

This cost estimate may not accurately represent specific conditions or equipment on a given project. Therefore, the resident engineer should complete his own cost estimate based on the location and equipment for his project pursuant to Section 5-300, of the *Construction Manual*.