REGIONAL WATER QUALITY CONTROL BOARD

REGION

CALTRANS DISTRICT

8

STORM WATER MANAGEMENT PROGRAM

REGIONAL WORK PLAN FOR FISCAL YEAR 2002/2003

REGION 9

San Diego Regional Water Quality Control Board

CTSW-RT-01-075



California Department of Transportation District 8 464 West Fourth Street – 6th Floor San Bernardino, California 92401-1400

April 1, 2002

CERTIFICATION REGIONAL WORK PLAN

California Regional Water Quality Control Board San Diego Region 9 Fiscal Year 2002/2003 April 1, 2002

California Department of Transportation District 8

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is true, accurate, and complete to the best of my knowledge and belief. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment of knowing violations. [40 CFR 122.22(d)]

Anne Mayer, District Director

| Secti | Section 1 Introduction | | 1-1 | |
|----------------------------------|---|---|-----|--|
| Secti | Section 2 District Personnel and Responsibilities | | 2-1 | |
| Secti | on 3 | District Facilities and Water Bodies | 3-1 | |
| Secti | on 4 | High Risk Areas | 4-1 | |
| Secti | on 5 | Implementation Activities | 5-1 | |
| LIST | OF TA | BLES | | |
| 2-1 | Depar | tment Storm Water Personnel and Responsibilities | 2-1 | |
| 2-2 | Signat | ory Authority for Key Documents | 2-2 | |
| 3-1 | Distric | et 8 Facilities | 3-1 | |
| 4-1 | High I | Risk Areas | 4-1 | |
| 5-1 | Distric | et 8 Anticipated Project Development/Construction Schedule | 5-2 | |
| 5-2 | Antici | pated Maintenance Activities and Other Management Practices | 5-4 | |
| 5-3 General Management Practices | | 5-6 | | |
| LIST | OF FIG | URES | | |
| 2-1 | Organ | izational Chart | 2-3 | |
| 3-1 | District 8 Facilities and Waterbodies 3-2 | | | |

1.0 INTRODUCTION

The purpose of the Regional Work Plans (RWPs) is to describe how the Department District will specifically implement the Statewide Storm Water Management Program (SWMP) within the jurisdiction of each Regional Water Quality Control Board during Fiscal Year 2002-2003 as required by the Department Statewide Storm Water NPDES Permit – Order No. 99-06-DWQ (Permit). Implementation activities will be conducted in accordance with the procedures presented in the SWMP. The RWP indicates how District storm water management practices will be modified to improve water quality protection based on evaluation of the previous studies and management activities.

The RWP provides region-specific information on Department facilities, water bodies, and Best Management Practices (BMPs), and monitoring programs according to the following sections:

- Section 1 Introduction;
- Section 2 Personnel and Responsibilities;
- Section 3 District Facilities and Water Bodies;
- Section 4 High Risk Areas; and
- Section 5 Implementation Activities.

2.0 DISTRICT PERSONNEL AND RESPONSIBILITIES

Portions of Department District 8 fall within the jurisdiction of the San Diego Regional Water Quality Control Board (coverage area). Organization charts for District 8 are included in Figures 2-1. Staff responsible for implementing the SWMP within the San Diego Regional Water Quality Control Board jurisdiction are listed in Table 2-1.

TABLE 2-1: THE DEPARTMENT STORM WATER PERSONNEL AND RESPONSIBILITIES

| Staff | Title | Phone Number | E-Mail Address | Responsibilities |
|----------------------|--|----------------|-----------------------------------|--|
| Paul Lambert | NPDES Storm Water Coordinator, Design Storm Water Coordinator | (909) 383-4948 | Paul_Lambert@do t.ca.gov | Primary contact for all storm water issues. Oversees all NPDES office employees within the Districts. |
| Walt Griffith | Construction Storm Water Coordinator | (909) 514-2402 | Walt_Griffith@dot. ca.gov | Conducts inspections to assist the RE in ensuring that storm water controls are implemented on construction sites and to assist the RE s in reviewing SWPPPs/WPCPs |
| Jim Dodd | Maintenance Storm Water Coordinator | (909) 383-4703 | Jim_Dodd@dot.ca. gov | Implementation of the policies, procedures, personnel and equipment of the District SWMP |
| Scott Neff | Engineering Services Storm Water Coordinator | (909) 383-6483 | Scott_Neff@dot.ca .gov | Primary contact for Hydraulic-related storm water issues. |
| Phillip Reynolds | Project Management Storm Water Coordinator | (909) 383-4960 | Phillip_Reynolds@ dot.ca.gov | Primary contact for Project Management- related storm water issues. |
| Chung-Yuan Wen | Operations Storm Water Coordinator | (909) 383-7549 | Chung- Yuan_Wen@dot.c a.gov | Primary contact for Operations-related storm water issues. |
| Michael Yarbrough | Right of Way Storm Water Coordinator | (909) 383-4581 | Michael_Yarbroug h@dot.ca.gov | Primary contact for Right of Way-related storm water issues. |
| Rosanna Roa | Environmental Planning Storm Water Coordinator | (909) 383-5917 | Rosanna_Roa@do t.ca.gov | Primary contact for Environmental Planning-related storm water issues. |
| Yong H. Kim | Planning Storm Water Coordinator | (909) 388-7027 | Yong_Kim@dot.ca .gov | Primary contact for Transportation Planning-related storm water issues. |
| Vacant | Resource Management Storm Water Coordinator | Vacant | Vacant | Primary contact for Resource Management-related storm water issues. |

In compliance with Permit Section M. 10. b, the following [individuals/positions] listed in Table 2-2 are authorized to sign the documents, reports and other information submitted by the District to either the State Water Resources Control Board or the Regional Water Quality Control Board(s).

TABLE 2-2: SIGNATORY AUTHORITY FOR KEY DOCUMENTS

| Positions | Documents Authorized for Signature |
|--|---|
| District Director | All |
| District NPDES Storm Water Coordinator | All District storm water related documents except Annual Report |
| | Certification |
| Design Senior Engineer | NOC |
| Construction Senior or Resident Engineer | SWPPP approval, NOCC |
| Maintenance Senior Env Planner | Maintenance activity reports |
| Maintenance Superintendent | Maintenance activity reports |




Figure 2-1: Organizational Structure of District 8 Storm Water Program


3.0 DISTRICT FACILITIES AND WATER BODIES

This section identifies Department facilities and water bodies within each District and Regional Board jurisdiction. A list of Department facilities, excluding roadways, is presented in Table 3-1. Maps showing the District 8 boundaries within the San Diego Regional Water Quality Control Board], and major roads and highways are presented on Figure 3-1.

TABLE 3-1: DISTRICT 8 FACILITIES

| СО | Route | PM | Name | Comments | | | |
|------|--------------|---------------------------|-------------------|----------|--|--|--|
| | - | ⊥ Maintenance Station | S | | | | |
| None | | | | | | | |
| | Vista Points | | | | | | |
| None | | | | | | | |
| | Commercia | Il Vehicle Enforceme | nt Facilities | | | | |
| RIV | 15 | R0.7 | Rainbow NB | | | | |
| | | Roadside Rest Areas | S | | | | |
| None | | | | | | | |
| | P | ark and Ride Facilitie | es | | | | |
| RIV | 15 | 6.6 | Rancho California | | | | |
| | San | d and Salt Staging A | reas | | | | |
| None | | | | | | | |
| | | Snow Storage Sites | | | | | |
| None | · | | | _ | | | |
| | Toll | Road and Bridge Pla | azas | | | | |
| None | | | | | | | |

Lists and maps of the Department of Water Resource Hydrologic Units located within the coverage area are presented in Appendix A of the SWMP. Specific information on Department facilities and water bodies may also be found at the following website: http://stormwater.water-programs.com



4.0 HIGH RISK AREAS

A list of high risk areas within District 8 is presented in Table 4-1. High risk areas are defined in the Section E.2 of the Permit to include areas such as locations where spills from Department owned right-of-ways, activities, or facilities can discharge directly to municipal or domestic water supply reservoirs or ground water percolation facilities. Additional sites may be added to the high-risk list based on discussion between the Regional Water Quality Control Board (RWQCB) and the Department. The Permit requires consideration of appropriate spill containment and spill prevention control measures for these areas.

In order to generate the list of high-risk municipal and domestic water supply reservoirs and ground water percolation facilities the Department first contacted known public and private water supply providers. From the information received, the Department determined which facilities were susceptible to a direct spill from a Department activity or facility. This determination was based on proximity between the water body and Department facility, use characteristics of the facilities, and the probable spill response time.

The Department will consider and implement spill containment and prevention control measures in accordance with the processes contained in the SWMP including Section 3 for BMP identification and implementation, Section 4.4.1 for new construction projects or Section 4.4.2 for retrofit projects that are within these areas.

TABLE 4-1: HIGH RISK AREAS

| Road Segment/ Facility | County | High Risk Area | Description | Comments |
|---------------------------|--------|----------------|-------------|----------|
| None | | | | |

5.0 IMPLEMENTATION ACTIVITIES

This section presents specific project work planned for the year and indicates BMP implementation improvements. The anticipated schedule of construction and maintenance activities is subject to change. The Department will discuss with the RWQCBs new projects meeting the criteria listed below when ground disturbance takes place or when significant maintenance activities are initiated during the year. These projects are updates to the RWP provided in April 2002.

Table 5-1 includes a list of construction projects that meet one or more of the following criteria:

- The project involves greater than 5 acres (1 acre after 2003) of land disturbance, designated as "SWPPP";
- The project affects a 303(d) listed water body within the project limits, designated as "303d";
- The project requires a 401 Water Quality Certification or Waiver, designated as "401":
- The project is a Supplemental Environmental Project (water quality project negotiated by the RWQCB and the Department) designated as "SEP";
- The project is a storm water retrofit project (SWMP Section 4.4.2), designated as "Retro";
- The project includes Lahontan Regional Water Quality Control Board specific requirements for the Lake Tahoe Hydrologic Unit, designated as "LT";
- The project limits are with a "High Risk Area," designated as "HR"; and
- The project is designated by a RWQCB as posing a potential threat to water quality, designated as "RB."

The information presented in Table 5-1 is intended to facilitate early RWQCB staff input in the project planning phase in accordance with Section L.8 of the Permit and Section 4.4 of the SWMP. The goal is to resolve water quality issues that may affect project funding, permitting, and scheduling. In addition, projects that require RWQCB review and approval of project SWPPPs/WPCPs in accordance with Sections H.8 and L.8 of the Permit are also covered in Table 5-1.

Table 5-2 presents a list of anticipated significant maintenance projects that have the potential to impact water quality and provides early notification of such activities. It also includes region-specific issues and BMP actions/modifications based on program evaluations discussed in current and/or past Annual Report(s).

Table 5-3 summarizes various program management activities that are part of the storm water pollution prevention program.

5-1

TABLE 5-1: DISTRICT 8 ANTICIPATED PROJECT DEVELOPMENT/CONSTRUCTION SCHEDULE

| | | | | | | | | | | Anticipated Schedule | Project De | evelopment | Constructio | n Period |
|-----|--------------------|--------|-----|-------|-----------|---|--------------------------------|------------|----------|-------------------------|---------------------------------|--|-------------|--------------------|
| No. | SWMP** Category | | Co. | Route | PM | | Water Bodies Affected | | | Scoping (PID) | Project Dev (PA&ED) Final | Final Design (PS&E) - Permits & Mitigation | | Completion Date |
| 1 | | 38350 | RIV | 074 | 62.9-63 | REPLACE BRIDGE | | SWPPP | 2.4 ACRE | 9/1/1999 | 4/1/2004 | 8/1/2005 | 2/1/2006 | 12/1/2006 |
| 2 | | 474400 | | | | | | SWPPP | 5 Hec | | 1/1/03 | 5/1/05 | 2/1/06 | 8/1/07 |
| 3 | В | 32780 | RIV | 215 | 12.3-12.8 | RECONSTRUCT IC | None | SWPPP | 53.0 | 4/12/2000 | 10/1/2001 | | | |
| 4 | D1a | 43280 | RIV | 215 | | RECONSTRUCT INTERCHANGE | None | SWPPP | 16.6 | 10/23/1997 | 10/23/1997 | 7/1/2002 | 6/1/2003 | 7/1/2004 |
| 5 | A | 45020 | RIV | 079 | | BRIDGE SCOUR MITIGATION | Temecula Creek | 401 | 0.124 | 11/4/1999 | 9/1/2002 | 4/1/2003 | 10/1/2003 | 4/1/2004 |
| 6 | В | 46460 | RIV | 079 | | WIDEN TO 4-LANE EXPRESSWAY/HIGH WAY | Range Creek San Diego Aqdt. | SWPPP, 401 | 30 | 8/26/1991 | 7/1/2001 | 3/1/2003 | 3/1/2004 | 6/1/2005 |
| 7 | C1b | 49530 | RIV | 015 | | REHABILITATE EXISTING CHECK DAM | Warm Sring Creek | 401 | | 10/20/1999 | 11/6/2000 | 6/8/2001 | 8/15/02 | 12/1/02 |

^{*} Criteria

Department Work Plans

5-2 April 1, 2002

SECTION FIVE Regional Work Plans

SWPPP = Greater than 5 acres of land disturbance

303d = 303 (d) listed water body within project limits and affected by project

= 401 Certification/Waiver required SEP = Supplemental Environmental Project
Retro = Storm Water Retrofit Project (SWMP 4.4.2)

= Lahontan RWQCB specific requirements for the Lake Tahoe Hydrologic Unit LT

= Project limits within High Risk Area HR

= RWQCB designated project as a potential threat to water quality

**SWMP Category is defined in SWMP Section 4.4.1, Table 4-3,

- (A) (B) Beginning of Project Development Process prior to approval of the PSR
- PSR approved but Environmental Documents are not final
- (C) (D) Environmental documents final
- Environmental documents final, design complete and project in the construction phase of project delivery

SECTION FIVE

TABLE 5-2: ANTICIPATED MAINTENANCE ACTIVITIES AND OTHER MANAGEMENT PRACTICES

| Significant | Significant Road Maintenance Activities (1) | | | | | | | |
|-------------|---|----|-------------|--------------------------|-------------|------------|--------------------|--|
| County | Route | PM | Description | Water Bodies Affected | Criteria(2) | Start Date | Completion Date | |
| NONE | | | • | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Maintenance Facility and Activity Inspections

For the year 2002-03 Beechers Corners, Burnt Mill, Essex, Hemet, Blythe, Keen Camp Maintenance Facilities will be inspected

Various maintenance activities will be inspected, they include paving, crack sealing, and shoulder backing

Maintenance Facility BMP Improvements

Magana / Ortega Maintenance Facility is getting a new material storage building for Special Crews

Maintenance BMP Actions/Modifications

Review FPPP at Maintenance Facilities. Determine its effectiveness. If there are deficiencies within the FPPP, then Maintenance will propose modifications for the following year.

Improve BMPs at Vactor sites

Improve BMP's at Material Storage areas.

Vegetation Management and Vegetated Slope Management

The District 8 Vegetation Control Plan (VCP) for FY 2002/03 is complete. The VCP goal is to minimize the discharge of the chemicals to receiving waters by reducing chemical use for vegetation control. The VCP includes the following major items:

- Type of chemical to be applied and form (dry or liquid)
- Application locations, lengths, widths, total area, rates, frequency, total amount
- Reason for application
- Mowing program

Department

Work Plans

April 1, 2002

TABLE 5-2: ANTICIPATED MAINTENANCE ACTIVITIES AND OTHER MANAGEMENT PRACTICES

| Vegetated Slope Evaluation | | | | | |
|----------------------------|----------|--------|---------------------|-------------------------------|--|
| | Route/PM | County | Inspection Schedule | Remediation Action Planned | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

(1) Significant road maintenance activities includes projects involving grade changes, additional hydraulic capacity, direct discharges to surface waters, increases in impervious surface area, or other activities identified or agreed to between RWQCB and the Department staff.

(2) Criteria

SWPPP = Greater than 5 acres of land disturbance

303d = 303 (d) listed water body with project limits and affected by project

401 = 401 Certification/Waiver required SEP = Supplemental Environmental Project

Retro = Storm Water Retrofit Project (SWMP 4.4.2)

LT = Lahontan RWQCB specific requirements for the Lake Tahoe Hydrologic Unit

HR = Project limits within High Risk Area

RB = RWQCB designated projects as a potential threat to water quality

5-6

TABLE 5-3: GENERAL MANAGEMENT PRACTICES

Monitoring Activities

Monitoring activities will be conducted in accordance with the statewide program described in the Storm Water Monitoring Plan FY 01/02.

Construction Compliance Monitoring Program

Construction activities are inspected through the Construction Compliance Monitoring Program (CCMP). Monitoring results are provided in the annual report. In addition to the CCMP, the District Construction Division conducts internal audits of construction sites. These audits "rate" the performance of the construction sites in the same fashion as the CCMP.

Training and Public Outreach

- 1. Training will be provided to Design Staff upon completion of the latest revision of the Project Planning and Design Guide
- 2. Training is an on going process for maintenance. All crews are shown the videos of (Storm Water Quality Training For Maintenance) Course # G31430. The Storm Water Coordinator gives training as needed to all maintenance crews regarding BMP's and environmental concerns. Field Supervisors train, review and document BMP's used on maintenance activities at facilities and in the field for maintenance employees. Storm water training is also given in conjunction with Hazmat training. Additional training will be provided as the new maintenance guidelines are completed. Supervisors and Superintendents receive additional Storm Water training at one of the training sessions at the Maintenance Academy in Kingvale. Maintenance Public Affair Officers distribute Storm Water literature provided from Headquarters' Environmental Section at various Maintenance functions, job fairs, Southern Equipment Roadeo, open houses, Route 66 Rendezvous, etc.
- 3. Training is an on going process for the Construction Division. All construction field office personnel have been through a 6 hr class, "Storm Water Control on Construction Projects "/#G0C017. All construction field office Seniors and Resident Engineers are also to attained a "Storm Water Control on Construction Projects Management" this class is currently being scheduled. For new employees and those who were unable to attend the original classes there will be additional classes scheduled. The District Construction Division conducts training sessions in the Districts field offices and provides assistance reviews in the same fashion as the CCMP.

SECTION FIVE Regional Work Plans

TABLE 5-3: GENERAL MANAGEMENT PRACTICES

District Storm Water Unit staff will again participate in the Environmental Expo, to be held at Cal State San Bernardino. Staff from the District Storm Water Unit will demonstrate the effects of all-too-common activities (excessive pesticide and fertilizer use, dumping used motor oil in stormdrains, poor erosion control practice, etc) on Non-point Source storm water pollution using the District's Enviroscape watershed model. Hand-outs describing the Department' Storm Water Program will be distributed.

The District Storm Water Unit will also demonstrate the Enviroscape watershed model as part of the District's "Bring your Child to Work Day". The model will be displayed for children of District employees between the ages of 6 and 16.

The District Storm Water Unit, with the assistance of the District Public Affairs Unit, will seek out additional public information opportunities at County Fairs, schools, and other public events.

Municipal Coordination

District Storm Water Unit staff will participate in monthly coordination meetings of the Riverside County/Murietta Creek MS4 Co-Permitees

REGIONAL WATER QUALITY CONTROL BOARD

REGION

CALTRANS DISTRICT

11

STORM WATER MANAGEMENT PROGRAM

REGIONAL WORK PLAN FOR FISCAL YEAR 2002/2003

REGION 9

San Diego Regional Water Quality Control Board

CTSW-RT-01-075



California Department of Transportation District 11 2829 Juan St San Diego, California 92186

APPROVAL REGIONAL WORK PLAN

California Regional Water Quality Control Board San Diego Region 9 Fiscal Year 2002/2003

April 1, 2002

California Department of Transportation District 11

| Charles "Muggs" Stoll | Deputy District Director- Environmental |
|-----------------------|---|
| | |
| Allan Kosup | Deputy District Director- Engineering A |
| William Valle | Deputy District Director- Engineering B |
| Richard A Hopkins | Deputy District Director- Design |
| Jim D Linthicum | Deputy District Director- Construction |
| Mike McManus | Deputy District Director- Maintenance |

CERTIFICATION REGIONAL WORK PLAN

California Regional Water Quality Control Board San Diego Region 9 Fiscal Year 2002/2003 April 1, 2002

California Department of Transportation Districts 11

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is true, accurate, and complete to the best of my knowledge and belief. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment of knowing violations. [40 CFR 122.22(d)]

PEDRO ORSO-DELGADO District Director

| Sectio | n 1 | 1 Introduction 1-1 | | | |
|-------------------------------------|---|--|-----|--|--|
| Sectio | on 2 Department Personnel And Responsibilities 2-1 | | | | |
| Section | ection 3 District Facilities And Water Bodies 3 | | | | |
| Section | Section 4 High Risk Areas | | 4-1 | | |
| Section 5 Implementation Activities | | Implementation Activities | 5-1 | | |
| LIST O | F TABL | ES | | | |
| 2-1 | Departi | ment Storm Water Personnel | 2-1 | | |
| 2-2 | Signato | ory Authority for Key Documents | 2-1 | | |
| 3-1 | District 11 Facilities 3-1 | | | | |
| 4-1 | High R | isk Areas | 4-1 | | |
| 5-1 | District | 11 Anticipated Project Development/Construction Schedule | 5-2 | | |
| 5-2 | Anticipated Maintenance Activities and Other Management Practices 5-8 | | | | |
| 5-3 | General Management Practices 5-9 | | | | |
| LIST OI | OF FIGURES | | | | |
| 2-1 | NPDES Organizational Chart 2-2 | | | | |
| 3-1 | San Di | ego Regional Board Jurisdictional Area | 3-4 | | |

SDRWQCB RWP

1.0 INTRODUCTION

The purpose of the Regional Work Plan (RWP) is to describe how the Department will specifically implement the Statewide Storm Water Management Program (SWMP) within the jurisdiction of each Regional Water Quality Control Board during Fiscal Year 02-03 as required by the The Department Statewide Storm Water NPDES Permit – Order No. 99-06-DWQ (Permit). Implementation activities will be conducted in accordance with the procedures presented in the SWMP. The RWP indicates how District storm water management practices will be modified to improve water quality protection based on evaluation of the previous studies and management activities.

The RWP provides region-specific information on Department facilities, water bodies, Best Management Practices (BMPs), and monitoring programs according to the following sections:

- Section 1 Introduction;
- Section 2 Personnel and Responsibilities;
- Section 3 District Facilities and Water Bodies;
- Section 4 High Risk Areas; and
- Section 5 Implementation Activities.

SDRWOCB RWP 1-1

2.0 DEPARTMENT PERSONNEL AND RESPONSIBILITIES

Portions of Districts 11 fall within the jurisdiction of the San Diego Regional Water Quality Control Board. Organization charts for District 11 are included in Figure 2.1, District 11 NPDES Team Organizational Chart. Staff responsible for implementing the SWMP in the San Diego Regional Water Quality Control Board include NPDES Program Manager, Cory Binns, District NPDES Coordinator, Sayra Ramos, and other responsible staff as appropriate. A list of the key contacts is provided in Table 2-1.

Staff Title **Phone Number** E-Mail Address Cory Binns Program Manager Cory Binns@dot.ca.gov (619) 688-3626 Sayra_Ramos@dot.ca.gov Sayra Ramos District NPDES Coordinator (619) 688-6430 Dave Stebbins District Design Storm (858)688-6676 David_Stebbins@dot.ca.gov Water Coordinator Michael_Kolbenschlag@dot.ca.gov District Construction Storm (858)467-4080 Michael Kolbenschlag Water Coordinator Barbara Ronimus District Maintenance Storm (619) 688-3325 Barbara_Ronimus@dot.ca.gov Water Coordinator

TABLE 2-1: DEPARTMENT STORM WATER PERSONNEL


In compliance with Permit Section M. 10. b, the following positions listed in Table 2-2 are authorized to sign the documents, reports and other information submitted by the District to either the State Water Resources Control Board or the Regional Water Quality Control Board.

| TARI F 2-2. | SIGNATORY | ALITHORITY FOR I | KEY DOCUMENTS |
|----------------|-----------|------------------|---------------|
| 1 A D L L 2-2. | | | ALI DOCUMENTO |

| Positions | Documents Authorized for Signature | | |
|----------------------------|--|--|--|
| NPDES Program Manager | All District Documents with except of Regional Work Plan (RWP) | | |
| | Notification of Construction (NOC) | | |
| District NPDES Coordinator | Notice of Completion of Construction (NOCC) | | |
| District NFDE3 Coordinator | Notice of Soil Reuse with Aerially Deposited Lead (ADL) | | |
| | Notice and Report of Non-Compliance | | |
| Construction Storm Water | Notice and Report of Non-Compliance for Construction Projects | | |
| Coordinator | | | |
| Maintenance Storm Water | Notice and Report of Non-Compliance for Maintenance Activities | | |
| Coordinator | | | |

SDRWOCB RWP 2-1

NPDES TEAM ORGANIZATIONAL CHART



3.0 DISTRICT FACILITIES AND WATER BODIES

This section identifies Department facilities and water bodies within each District and Regional Board jurisdiction. A list of Department facilities, excluding roadways, is presented in Table 3-1. Maps showing District 11 boundaries within the San Diego Regional Board and major roads and highways are presented on Figure 3-1.

TABLE 3-1: DISTRICT 11 FACILITIES

| CO | RTE | PM | NAME | DESCRIPTION | | | | | | |
|----|-----|-------|----------------------|-------------------------------------|--|--|--|--|--|--|
| | | | MAINTENANCE S' | TATIONS | | | | | | |
| SD | 2 7 | | | | | | | | | |
| SD | 5 | 20.1 | Pacific Hwy | Landscape Maintenance | | | | | | |
| SD | 5 | 47 | Carlsbad | Highway Maintenance | | | | | | |
| SD | 8 | 4.4 | Camino Del Rio | Landscape Maintenance | | | | | | |
| SD | 8 | 38 | Descanso | Highway Maintenance | | | | | | |
| SD | 15 | 12.5 | Chollas | Structural Bridge Operations | | | | | | |
| SD | 52 | 0 | Santee | Highway Maintenance | | | | | | |
| SD | 75 | 20.3 | Coronado Toll Bridge | Highway Maintenance | | | | | | |
| SD | 78 | 16 | Escondido | Highway Maintenance | | | | | | |
| SD | 79 | 28.3 | Lake Henshaw | Highway Maintenance | | | | | | |
| SD | 805 | 12.3 | Imperial | Landscape Maintenance | | | | | | |
| SD | 805 | 21.8 | Kearny Mesa | Highway Maintenance | | | | | | |
| SD | 905 | 3.8 | Otay | Landscape Maintenance | | | | | | |
| | | COM | MERCIAL VEHICLE ENFO | RCEMENT FACILITIES | | | | | | |
| SD | 5 | R67.1 | San Onofre | NB | | | | | | |
| SD | 5 | R67.4 | San Onofre | SB | | | | | | |
| SD | 15 | 53.5 | Rainbow | Southbound (SB) | | | | | | |
| SD | 905 | 12 | Otay Mesa | Northbound (NB) | | | | | | |
| | | | VISTA POIN | ITS | | | | | | |
| SD | 5 | 39.1 | Manchester | Vista Point | | | | | | |
| SD | 5 | 63.7 | Las Flores | Vista Point | | | | | | |
| SD | 8 | 35.5 | Viejas Grade | Vista Point | | | | | | |
| | | | PARK AND RIDE FA | ACILITIES | | | | | | |
| SD | 5 | 39.8 | Birmingham | NE corner Birmingham Dr in Cardiff | | | | | | |
| SD | 5 | 26.8 | Gilman Dr | SW corner Gilman Dr IC | | | | | | |
| SD | 5 | 32.9 | Carmel Valley | SW corner Carmel Valley Rd | | | | | | |
| SD | 5 | 44-45 | La Costa | NE, 710 La Costa Ave. | | | | | | |
| SD | 8 | 9.7 | La Mesa | SE corner Alvarado Rd & 70th St | | | | | | |
| SD | 8 | 12.7 | Fuerte Dr | SW corner I-8 & Fuerte Dr | | | | | | |
| SD | 8 | 14.2 | Murray | S side Murray Dr abutting Route 8 | | | | | | |
| SD | 8 | 20.1 | Camino Canada | SE corner Camino Canada in Glenview | | | | | | |
| SD | 8 | 21.8 | Lake Jennings | NE corner Lake Jennings Park Rd | | | | | | |
| SD | 8 | 37.8 | Japatul Valley | NW corner Japatul Valley Rd | | | | | | |
| SD | 8 | 11-12 | Severin-Bancroft | SW, 5480 Bancroft Dr | | | | | | |

| | PARK AND RIDE FACILITIES CONTINUED | | | | | | | | | | | |
|----|------------------------------------|----------|---------------------------|---------------------------------------|--|--|--|--|--|--|--|--|
| CO | RTE | PM | NAME | DESCRIPTION | | | | | | | | |
| SD | 8 | 12-13 | Severin-Murray | NE, 9307 Murray Dr | | | | | | | | |
| SD | 8 | 17-18 | E. Main- Madison | NE, 1470 East Madison | | | | | | | | |
| SD | 8 | 0.99 | Taylor | SW, 4300 Taylor St. | | | | | | | | |
| SD | 8 | 21.7 | Los Coches | SE,13702 Camino Canada | | | | | | | | |
| SD | 8 | 8.7 | 70th Alvarado | SE, 7100 Alvarado | | | | | | | | |
| SD | 15 | 15.8 | Mira Mesa | NW, 4929 Mira Mesa | | | | | | | | |
| SD | 15 | 15.8 | Mira Mesa | NW corner Mira Mesa IC | | | | | | | | |
| SD | 15 | 18.2 | Community Rd | SW of Community & Twin Peaks Rd | | | | | | | | |
| SD | 15 | 18.2 | | SW corner Rancho Penasquitos Blvd | | | | | | | | |
| | 15 | 21.2 | Penasquitos | * | | | | | | | | |
| SD | 15 | 32.9 | Elephant Bar | West Bernardo Dr | | | | | | | | |
| SD | | | El Norte Pkwy | SE corner El Norte Pkwy IC | | | | | | | | |
| SD | 15 | 15-16 | Black Mtn | Black Mtn at Hillery Dr | | | | | | | | |
| SD | 15 | 18-19 | Poway-Sabre Springs | NW 12668 Sabre Spring Blvd (mall) | | | | | | | | |
| SD | 15 | 23.5 | Rancho Bernardo | NW, Rancho Bernardo Rd | | | | | | | | |
| SD | 15 | 36.5 | Deer Springs Rd | Deer Springs Rd at Serendipity Lane | | | | | | | | |
| SD | 15 | 39.3 | Mt. Meadows Rd | Mt. Meadows Rd at Champagne Blvd | | | | | | | | |
| SD | 15 | 40.8 | Gopher Canyon Rd | Gopher Canyon Rd/Champagne Blvd | | | | | | | | |
| SD | 15 | 26.7 | Via Rancho Pkwy | North County Fair | | | | | | | | |
| SD | 52 | 13-14 | Mission Gorge/Big Rock Dr | SE, Santee | | | | | | | | |
| SD | 54 | 2.5 | Jamacha Blvd | S side Jamacha Blvd near Sweetwater | | | | | | | | |
| SD | 54 | 15 | Washington Ave | S side near Jamacha Rd | | | | | | | | |
| SD | 54 | 16 | Madison in El Cajon | N side near Main St | | | | | | | | |
| SD | 56 | 0.7 | Rancho Carmel | NE,10155 Rancho Carmel Dr. | | | | | | | | |
| SD | 56 | 0.3 | Ted Williams Pkwy | Ted Williams Pkwy/Sabre Springs Pkwy | | | | | | | | |
| SD | 67 | 3.9 | Riverford Dr. | NE, 11575 Woodside Ave | | | | | | | | |
| SD | 67 | 5.5 | Mapleview | NE,12522 Mapleview | | | | | | | | |
| SD | 76 | 17.3 | Hwy 76 - I-15 | NW | | | | | | | | |
| SD | 76 | 2-3 | Mission Ave/Frontier Dr | SE, Oceanside | | | | | | | | |
| SD | 78 | 3.3 | College (South) | SE, 3700 Haymer | | | | | | | | |
| SD | 78 | 6.9 | Sunset | SW, 501 Seaview Place | | | | | | | | |
| SD | 78 | 3-4 | Hwy 78-College(North) | NW | | | | | | | | |
| SD | 78 | 5.9 | Broadway | SW, 871 North Broadway | | | | | | | | |
| SD | 94 | 12.8 | Sweetwater Springs | NE, 3642 Agua Dulce | | | | | | | | |
| SD | 94 | 8-9 | Lemon Grove High | SW, 7675 High St. | | | | | | | | |
| SD | 125 | 13-14 | Bancroft-Grossmont | SW, 5230 Bancroft Dr | | | | | | | | |
| SD | 805 | 8.6 | Sweetwater | SE, 2300 Sweetwater Rd | | | | | | | | |
| SD | 805 | 24.4 | Governor | NW, 5196 Governor Dr | | | | | | | | |
| SD | 805 | 26.9 | Mira Mesa | NE | | | | | | | | |
| | 1 | | SAFETY ROADSIDE I | | | | | | | | | |
| SD | 5 | R59.4/R6 | Aliso Creek | 5.8 mi. N of Oceanside; NB & SB | | | | | | | | |
| SD | 8 | R49 | Buckman Springs | 3.3 mi. E of Pine Valley | | | | | | | | |
| | | 1017 | TOLL ROAD AND TOLL I | , , , , , , , , , , , , , , , , , , , | | | | | | | | |
| SD | 75 | 20.284 | San Diego/Coronado | San Diego – Coronado Bridge | | | | | | | | |
| עט | 13 | 20.204 | San Diego/Coronado | Dan Diego – Coronado Driago | | | | | | | | |

Lists and maps of the Department of Water Resource Hydrologic Units located within the coverage area are presented in Appendix A of the SWMP. Specific information on Department facilities and water bodies may also be found at the following website: http://stormwater.water-programs.com

4.0 HIGH RISK AREAS

A list of high risk areas within District 11 is presented in Table 4-1. High risk areas are defined in the Section E.2 of the Permit to include areas such as locations where spills from Department owned right-of-ways, activities, or facilities can discharge directly to municipal or domestic water supply reservoirs or ground water percolation facilities. Additional sites may be added to the high-risk list based on discussion between the Regional Water Quality Control Board (RWQCB) and Department. The Permit requires consideration of appropriate spill containment and spill prevention control measures for these areas.

In order to generate the list of high-risk municipal and domestic water supply reservoirs and ground water percolation facilities the Department first contacted known public and private water supply providers. From the information received, the Department determined which facilities were susceptible to a direct spill from a Department activity or facility. This determination was based on proximity between the water body and the Department facility, use characteristics of the facilities, and the probable spill response time.

The Department will consider and implement spill containment and prevention control measures in accordance with the processes contained in the SWMP including Section 3 for BMP identification and implementation, Section 4.4.1 for new construction projects or Section 4.4.2 for retrofit projects that are within these areas.

TABLE 4-1: HIGH RISK AREA

| Road Segment/ Facility | County | High Risk Area | Description |
|---------------------------|--------|----------------|--|
| I-15 | SD | Lake Hodges | Water supply reservoir for City of San |
| | | | Diego |

SDRWOCB RWP 4-1

5.0 IMPLEMENTATION ACTIVITIES

This section presents specific project work planned for the year and indicates BMP implementation improvements. The anticipated schedule of construction and maintenance activities is subject to change. Department will discuss with the RWQCBs new projects meeting the criteria listed below when ground disturbance takes place or when significant maintenance activities are initiated during the year. These projects are updates to the RWP provided in April.

Table 5-1 includes a list of construction projects that meet one or more of the following criteria:

- The project involves greater than 5 acres (1 acre after 2003) of land disturbance, designated as "SWPPP";
- The project affects a 303(d) listed water body within the project limits, designated as "303d";
- The project requires a 401 Water Quality Certification or Waiver, designated as "401";
- The project is a Supplemental Environmental Project (water quality project negotiated by the RWQCB and Department) designated as "SEP";
- The project is a storm water retrofit project (SWMP Section 4.4.2), designated as "Retro";
- The project includes Lahontan Regional Water Quality Control Board specific requirements for the Lake Tahoe Hydrologic Unit, designated as "LT";
- The project limits are with a "High Risk Area," designated as "HR"; and
- The project is designated by a RWQCB as posing a potential threat to water quality, designated as "RB."

The information presented in Table 5-1 is intended to facilitate early RWQCB staff input in the project planning phase in accordance with Section L.8 of the Permit and Section 4.4 of the SWMP. The goal is to resolve water quality issues that may affect project funding, permitting, and scheduling. In addition, projects that require RWQCB review and approval of project SWPPPs/WPCPs in accordance with Sections H.8 and L.8 of the Permit are also covered in Table 5-1.

Table 5-2 presents a list of anticipated significant maintenance projects that have the potential to impact water quality and provides early notification of such activities. It also includes region-specific issues and BMP actions/modifications based on program evaluations discussed in current and/or past Annual Report(s).

Table 5-3 summarizes various program management activities that are part of the storm water pollution prevention program.

TABLE 5-1: DISTRICT 11 ANTICIPATED PROJECT DEVELOPMENT/CONSTRUCTION SCHEDULE

| | | EA# | | | | | Water Bodies Affected | Criteria* | | Anticipated | d Project Dev Schedule | velopment | Construction Period | |
|-----|--------------------|-------|-----|-------|------------------|---------------------------------------|---------------------------|------------|--------------------------------|--|--|--|---------------------|--------------------|
| No. | SWMP category** | | Co. | Route | Post Mile | Description | | | Land Disturbance Acreage | Project Scoping (PID) Preliminary Env. Evaluation | Project Dev. (PA&ED) - Draft EIS/EIR | Final Design (PS&E) - Permits & Mitigation | Start Date | Completion Date |
| 1 | В | 17282 | SD | 56 | 2.1 - 6.3 | CONST 4-LANE FWY | Penasquitos Creek | SWPPP 303d | 169.40 | | | 1/16/02 | 7/31/02 | 12/2/04 |
| 2 | В | 23260 | SD | 15 | 13.1M - 16.8M | CONST ADDED LANES | | SWPPP | | 9/23/98 | 1/4/02 | 3/25/02 | 12/2/02 | 1/3/07 |
| 3 | В | 23910 | SD | 5506 | - | CONSTRUCT DISTRICT OFFICE BUILDING | San Diego Bay | SWPPP | | | 10/2/01 | 8/8/02 | 4/20/03 | 8/18/05 |
| 4 | В | 07860 | SD | 5 | 8.6 - 10.0R | REPLACE PLANTING | | SWPPP | | 9/15/99 | 5/31/02 | 2/20/03 | 8/10/03 | 2/1/08 |
| 5 | В | 06481 | SD | 15 | 18.8M - 28.1M | CONSTRUCT MANAGED LANES (STAGE 1) | | SWPPP 401 | | 9/23/98 | | 3/26/03 | 12/28/03 | 12/31/09 |
| 6 | В | 06484 | SD | 15 | 18.8M - 28.1M | NOISE MITIGATION FOR HOV/MANAGED | | SWPPP 401 | | 9/23/98 | | 10/5/03 | 6/16/04 | 7/6/07 |
| 7 | В | 00320 | SD | 78 | 1.5 - 3.3 | CONST TRUCK CLIMBING LANE | | SWPPP | | | 1/1/03 | 1/27/04 | 6/18/04 | 2/18/06 |
| 8 | В | 06510 | SD | 5 | 34.8R - 35.7R | CONST AUXILIARY LANE N/B | | 401 | | 10/9/97 | 9/15/02 | 1/8/04 | 6/24/04 | 12/21/04 |
| 9 | В | 06500 | SD | 5 | 29.5R - 30.1R | CONST AUXILIARY LANE S/B | Los Penasquitos lagoon | 303d | | | 2/11/03 | 7/13/04 | 10/31/04 | 8/27/05 |
| 10 | В | 06380 | SD | 8 | 17.4 - 18.7R | CONST AUXILIARY LANE-E/B & REPLACE | | SWPPP | | 10/10/97 | 1/11/03 | 10/20/04 | 5/29/05 | 3/19/08 |
| 11 | В | 06670 | SD | 5 | 10.0R - 10.7R | CONSTRUCT AUXLIARY LANE | | 401 | | 12/30/98 | 7/7/03 | 4/7/05 | 11/7/05 | 12/9/06 |

| | | | | | | 2 | Water Bodies | | Land | Anticipated | Project Deve Schedule | lopment | Construction Period | |
|-----|--------------------|-------|-----|-------|------------------|--|---|-------------------|------------------------|--|--------------------------|--|---------------------|--------------------|
| No. | SWMP category** | EA# | Co. | Route | Post Mile | Description | Affected | Criteria* | Disturbance Acreage | Project Scoping (PID) Preliminary Env. Evaluation | Draft | Final Design (PS&E) - Permits & Mitigation | Start Date | Completion Date |
| 12 | В | 09316 | SD | 905 | 5.7 - 12 | CONST 6-LANE FWY | | 401 | | | 4/15/03 | 8/22/05 | 5/22/06 | 1/11/09 |
| 13 | В | 14665 | SD | 94 | 10 - 11.8R | OUTSIDE LANE WIDENING/CONST FWY | | SWPPP | | 10/18/01 | 9/22/05 | 8/4/06 | 5/8/07 | 11/28/10 |
| 14 | В | 05630 | SD | 11 | 0 - 2.7 | CONSTRUCT 4-LANE FREEWAY | Otay River | 401 | | 9/28/00 | 6/26/05 | 8/23/06 | 6/19/07 | 12/5/09 |
| 15 | В | 08030 | SD | 94 | 0 - 10.3 | SR 94 CAPACITY ENHANCEMENT PROJECT | | 401 | | | 10/14/07 | 7/14/08 | 4/13/09 | 8/30/13 |
| 16 | В | 23580 | SD | 5 | 34.1R - 54.6R | CONST HOV/GENERAL PURPOSE/AUX LANES | | 401 | | 1/31/00 | 6/4/07 | 12/2/09 | 2/7/13 | 2/8/15 |
| 17 | В | 06480 | SD | 15 | 10.7R - 31.8R | CONST MANAGED LANES | | swppp 401 | | 9/23/98 | 10/15/02 | | | |
| 18 | В | 24540 | SD | 5 | 13.8R - 14.3R | UPGRADE PLANTING/MURAL | San Diego Bay | 303d | | | 4/30/02 | 12/21/02 | | 6/4/05 |
| 19 | В | 24910 | SD | 54 | 0 - 1.9 | UPGRADE PLANTING | Sweetwater River | SWPPP | | | 11/15/02 | 6/28/03 | | 12/10/05 |
| 20 | С | 06520 | SD | 5 | 24.1R - 25.8R | CONST AUXILIARY LANE | Mission Bay | SWPPP 303d | 7.40 | | 3/14/00 | 3/17/00 | 8/8/00 | 6/30/04 |
| 21 | С | 2379U | SD | 15 | 2.3 - 06.1R | INSTALL TRANSPORTATION SYSTEMS | Chollas Creek and San Diego River | 303d | 3.00 | | 8/26/99 | 4/28/00 | 12/26/00 | 8/31/02 |
| 22 | С | 07241 | SD | 15 | 12.1M - 19.5M | INSTALL FIBER OPTIC CLOSED CIRCUIT | Penasquitos Creek | SWPPP 303d | 10.00 | | 1/30/01 | 5/18/01 | 10/18/01 | 10/17/05 |
| 23 | С | 0301U | SD | 5 | 28.3R - 37.0R | WIDEN FREEWAY AND BRIDGES | Los Penasquitos Lagoon | SWPPP 303d 404 | 153.00 | | | 5/10/01 | 3/18/02 | 3/19/07 |

| | | | | | | e Description | Water Bodies Affected | | Land | Anticipated | Project Deve Schedule | lopment | Construction Period | |
|-----|--------------------|-------|-----|-------|------------------|------------------------------------|--------------------------|------------|------------------------|--|--------------------------|--|---------------------|--------------------|
| No. | SWMP category** | EA# | Co. | Route | Post Mile | | | Criteria* | Disturbance Acreage | Project Scoping (PID) Preliminary Env. Evaluation | Draft | Final Design (PS&E) - Permits & Mitigation | Start Date | Completion Date |
| 24 | С | 01140 | SD | 125 | 11.2 - 12.1 | REPLCE PLANTNG PORTION OF ESA | Sweetwater River | SWPPP | 22.00 | 6/30/98 | 10/30/98 | 11/28/01 | 5/13/02 | 3/8/06 |
| 25 | С | 17641 | SD | 94 | 17 - 19.7 | REPLACE PLANTING PORTION OF | Sweetwater River | SWPPP | 11.30 | 1/3/01 | 6/27/01 | 2/8/02 | 7/24/02 | 7/24/06 |
| 26 | С | 07080 | SD | 15 | 06.5R - 10.8R | REPLACE PLANTING | | SWPPP | 7.40 | | 9/28/01 | 2/16/02 | 8/15/02 | 8/15/03 |
| 27 | С | 07580 | SD | 5 | 20.2R - 24.1R | CONST MEDIAN BARRIER | | SWPPP | | 8/31/99 | 6/18/01 | 2/9/02 | 9/12/02 | 7/8/04 |
| 28 | С | 16573 | SD | 78 | 72.9 - | BRIDGE WIDENING & RAIL UPGRADES | | 401 | | 10/7/97 | 12/22/00 | 6/23/02 | 12/20/02 | 12/10/03 |
| 29 | С | 23261 | SD | 15 | 17.5M - 18.0M | CONST AUXILIARY LANE (S/B) | | 401 | | 9/23/98 | | 1/6/03 | 9/15/03 | 4/6/08 |
| 30 | С | 01061 | SD | 52 | 14.7 - 16.3 | CONST 4-LANE FWY | | SWPPP | | | 7/1/98 | 7/20/03 | 9/2/04 | 4/10/07 |
| 31 | С | 09180 | SD | 905 | 11.1R - 11.6R | CONST INTERCHANGE | | SWPPP | | | 4/28/00 | 12/27/04 | 9/19/05 | 10/25/07 |
| 32 | С | 01062 | SD | 52 | 16.2 - 17.7 | CONST 4-LANE FWY | | 401 | | | 7/1/98 | 2/8/07 | 7/28/07 | 11/29/10 |
| 33 | D | 05910 | SD | 5 | 47.4R - 48.6R | REVISE INTERCHANGE | Pacific Ocean | SWPPP | 42.00 | | 12/31/89 | 7/22/97 | 12/9/97 | 1/31/02 |
| 34 | D | 06600 | SD | 94 | 6.2 - 08.8R | PLANTING, IRRIGATION AND PAVING | Chollas Creek | SWPPP 303d | 25.00 | | | 9/17/97 | 3/15/98 | 10/14/99 |

| | | | | | | e Description | Water Bodies Affected | | Land | | Project Deve Schedule | lopment | Construction Period | |
|-----|--------------------|-------|-----|-------|------------------|---|---|------------|------------------------|--|---|--|---------------------|--------------------|
| No. | SWMP category** | EA# | Co. | Route | Post Mile | | | Criteria* | Disturbance Acreage | Project Scoping (PID) Preliminary Env. Evaluation | Project Dev. (PA&ED) - Draft EIS/EIR | Final Design (PS&E) - Permits & Mitigation | Start Date | Completion Date |
| 35 | D | 02220 | SD | 5 | 31.8R - 34.8R | PLANTING AND IRRIGATION | Carmel Valley Creek/Los Penasquitos | SWPPP 303d | 104.00 | | | 11/17/97 | 7/31/98 | 4/1/02 |
| 36 | D | 06461 | SD | 5 | 12.1R - 14.1R | FIBER OPTICS CLOSED CIRCUIT TV | Chollas Creek | SWPPP 303d | 7.00 | | | 6/4/98 | 1/22/99 | 8/15/01 |
| 37 | D | 06980 | SD | 15 | 09.4R - 14.3M | RECLAIMED WATER CONVERSION | San Diego River | SWPPP | 112.00 | | 6/11/98 | 12/10/98 | 4/28/99 | 4/30/03 |
| 38 | D | 06570 | SD | 805 | 8.7 - 9.7 | REPLCE PLANTNG AND IRRIGATION | Sweetwater River | SWPPP | 53.00 | | | 12/1/98 | 6/4/99 | 9/30/04 |
| 39 | D | 05461 | SD | 75 | 13.5 - 17.5 | PLANTING AND IRRIGATION | San Diego Bay | SWPPP 303d | 123.60 | | | 7/11/98 | 6/24/99 | 7/1/04 |
| 40 | D | 23470 | SD | 15 | 4.8 - 4.9 | HIGHWAY PLANTING AND IRRIGATION | Chollas Creek | SWPPP 303d | 5.00 | | 7/10/95 | 12/2/98 | 6/30/99 | 7/31/02 |
| 41 | D | 0479K | SD | 5 | 8.6 - 9.4 | CONSTRUCT BIKE PATH AND BARRIER | Sweetwater River | 401 | 4.00 | | 9/16/98 | 3/3/99 | 8/31/99 | 7/30/02 |
| 42 | D | 07020 | SD | 94 | 3.7 - 4.6 | PLANTING AND IRRIGATION | Chollas Creek | SWPPP 303d | 87.00 | | 10/9/98 | 3/31/99 | 9/10/99 | 8/31/03 |
| 43 | D | 04807 | SD | 15 | 00.5R - 1.8 | CLOSE RAMPS AND CONSTRUCT EXTENSION | San Diego Bay/Chollas Creek | SWPPP 303d | 75.00 | | | 12/1/98 | 11/12/99 | 1/1/04 |
| 44 | D | 22440 | SD | 805 | 22.6 - 26.1 | EROSION CONTROL | San Diego River | SWPPP | 20.00 | | 9/10/98 | 6/29/99 | 11/12/99 | 10/31/02 |

| | | | | | | | Water Bodies | | Land | Anticipated | Project Deve Schedule | lopment | Construc | tion Period |
|-----|--------------------|-------|-----|-------|------------------|--|------------------------------------|------------|------------------------|--|---|--|------------|--------------------|
| No. | SWMP category** | EA# | Co. | Route | POST WITE | | Affected | Criteria* | Disturbance Acreage | Project Scoping (PID) Preliminary Env. Evaluation | Project Dev. (PA&ED) - Draft EIS/EIR | Final Design (PS&E) - Permits & Mitigation | Start Date | Completion Date |
| 45 | D | 17283 | SD | 56 | 6.3 - 7.4 | CONST 4-LANE FWY & INTERCHANGE | | 401 | | | | | 12/9/99 | 10/13/02 |
| 46 | D | 0486A | SD | 15 | 04.0R - 05.8R | HIGHWAY PLANTING AND IRRIGATION | Chollas Creek | SWPPP 303d | 28.00 | | 10/23/98 | 12/28/99 | 7/11/00 | 7/31/04 |
| 47 | D | 14702 | SD | 78 | 12.7 - 13.5 | REVISE INTERCHANGE | San Marcos Creek | SWPPP 303d | 20.00 | | 12/30/99 | 4/26/00 | 8/25/00 | 10/18/02 |
| 48 | D | 07800 | SD | 94 | 1.4 - 10.1T | PAVEMENT REHABILITATION | Chollas Creek | 303d | 2.72 | | 4/4/99 | 3/1/00 | 9/15/00 | 11/30/01 |
| 49 | D | 02192 | SD | 75 | 20.5R - 22.0R | SEISMIC RETROFIT - TOLL BRIDGE | San Diego Bay | 303d | 4.50 | | 8/12/99 | 4/21/00 | 10/23/00 | 1/4/02 |
| 50 | D | 17850 | SD | 78 | 35.5 - 37.3 | PAVEMENT REHABILITATION | Hatfield Creek | 401 | 0.85 | | 6/4/98 | 5/18/00 | 11/8/00 | 4/1/02 |
| 51 | D | 06610 | SD | 805 | 9.7 - 13 | PLANTING AND IRRIGATION | Chollas Creek | SWPPP 303d | 20.00 | 10/14/97 | | 4/5/00 | 11/21/00 | 9/13/02 |
| 52 | D | 01073 | SD | 125 | 19 - 21.3 | CONSTRUCT NEW MULTILANE HIGHWAY | Alvarado Creek, San Diego River | SWPPP | 70.00 | | | 12/31/99 | 12/8/00 | 1/1/05 |
| 53 | D | 07340 | SD | 15 | 20.1M - 21.2M | WIDEN AND UPGRADE EXISTING FREEWAY | Los Penasquitos Lagoon | SWPPP 303d | 104.00 | | 10/8/99 | 4/28/00 | 12/8/00 | 4/30/03 |
| 54 | D | 17640 | SD | 94 | 17.1 - 17.8R | UPGRADE SHOULDERS AND INTERSECTIONS | Sweetwater River | 401 | 4.80 | | 10/17/98 | 4/27/00 | 12/26/00 | 11/30/02 |
| 55 | D | 07100 | SD | 5 | 12.0R - 13.1R | REPLACE PLANTING AND IRRIGATION | Chollas Creek | SWPPP 303d | 30.00 | 10/1/97 | 6/29/00 | 11/30/00 | 4/19/01 | 8/29/04 |
| 56 | D | 06910 | SD | 5 | 19.4R - 20.1R | REPLACE PLANTING AND IRRIGATION | San Diego River | SWPPP | 10.00 | 12/17/99 | 1/27/00 | 11/6/00 | 4/24/01 | 2/28/02 |

SDRWQCB RWP 5-6

SECTION FIVE Regional Work Plans

| | | - 4 " | • | | Post Mile | Description | Water Bodies | | Land | | Project Deve Schedule | lopment | Construc | tion Period |
|-----|--------------------|--------------|-----|-------|------------------|---------------------------------------|------------------------------------|------------|------------------------|--|---|--|------------|--------------------|
| No. | SWMP category** | EA# | Co. | Koute | | · | Affected | Criteria* | Disturbance Acreage | Project Scoping (PID) Preliminary Env. Evaluation | Project Dev. (PA&ED) - Draft EIS/EIR | Final Design (PS&E) - Permits & Mitigation | Start Date | Completion Date |
| 57 | D | 0696U | SD | 52 | 0.4 - 3 | HIGHWAY PLANTING AND RESTORATION | San Clemente Canyon Creek | 303d SWPPP | 104.00 | 10/10/97 | 12/20/99 | 4/20/01 | 8/23/01 | 4/1/02 |
| 58 | D | 17432 | SD | 8 | 26.4R - 32.0R | WIDEN BRIDGES AND SEISMIC RETROFIT | Viejas Creek | 401 | 2.00 | 2/21/99 | 9/22/99 | 1/24/01 | 8/23/01 | 1/15/03 |
| 59 | D | 0019U | SD | 125 | 13.7 - 14.0L | CONSTRUCT FREEWAY AND INTERCHANGE | Sweetwater River | SWPPP | 123.00 | | 2/1/01 | 4/24/01 | 10/18/01 | 9/28/02 |
| 60 | D | 00192 | SD | 125 | 11.2 - 12.2 | CONSTRUCT HIGHWAY & BRIDGES | Sweetwater River | SWPPP | 6.10 | 10/30/98 | | 5/25/01 | 11/7/01 | 6/29/04 |
| 61 | D | 23471 | SD | 15 | 5.4 - 5.6 | PLANTING AND IRRIGATION | San Diego River | SWPPP | 5.00 | 1/6/00 | 1/6/00 | 4/16/01 | 12/27/01 | 6/10/03 |
| 62 | D | 00193 | SD | 125 | 12.1 - 13.7 | CONSTRUCT 6 LANE FREEWAY | Sweetwater River | SWPPP | 11.30 | | 6/30/00 | 11/26/01 | 5/5/02 | 9/1/07 |
| 63 | D | 23900 | SD | 15 | 27.3M - 33.6R | CONSTRUCT MEDIAN BARRIER | Escondido Creek and Lake Hodges | 303d | 4.90 | 11/18/99 | 11/18/99 | 1/27/02 | 12/17/02 | 5/28/04 |

* Criteria

SWPPP = greater than 5 acres of land disturbance (1 acre after March 2003)

303d = 303 (d) listed 401 = 401 Cert,

SEP = Supplemental Environmental Project
Retro = Storm Water Retrofit Project (SWMP 4.4.2)

LT = Lahontal RWQCB specific requirements for the Lake Tahoe Hydrologic Unit

HR = High Risk Area Present

RB = RWQCB designated projects posing a threat to water quality

**SWMP Category is defined in SWMP Section4.4.1, Table 4-3,

- (A) Beginning of Project Development Process prior to approval of the PSR
- (B) PSR Approved but Environmental Documents are not final
- (C) Environmental Documents final
- (D) Environmental documents final, design complete and project in the construction phase of project delivery.

SDRWQCB RWP

TABLE 5-2: ANTICIPATED MAINTENANCE ACTIVITIES AND OTHER MANAGEMENT PRACTICES

| Significant Road Maintenance Activities (1) | | | | | | | | | | | | |
|---|-------|----|---|--------------|-------------|------------|-----------------|--|--|--|--|--|
| | _ | | | Water Bodies | | | Completion | | | | | |
| County | Route | PM | Description | Affected | Criteria(2) | Start Date | Date | | | | | |
| SD | • | | Drain Inlet Inspection and Cleaning as required | | | June 2002 | October 1, 2002 | | | | | |

Maintenance Facility and Activity Inspections

All Maintenance Facilities within District 11are scheduled for annual inspections by the District Storm Water Coordinator.

Maintenance Facility BMP Improvements

Chula Vista and Kearny Mesa Maintenance Stations are being looked at for storm water improvements. The project is currently in the planning phase.

Vegetation Management and Vegetated Slope Management

The District 11 Vegetation Control Plan (VCP) for FY 2002/03 is under development. The VCP Goal is to minimize the discharge of chemicals to receiving waters by reducing the chemical use for vegetation control. The VCP includes the following major items:

- Types of chemical to be applied and form (dry or liquid)
- Application locations, lengths, widths, total area, rates, frequency, total amount
- Reason for application
- Mowing program

Districts will provide the VCP for FY02/03 to the RWQCB by May 15, 2002.

The Department's Maintenance Inspection and Slope Stabilization Team (MISST) created a Preliminary Slope Inspection Form, further discussed in Annual Report Section 5.2.3, that will be used to inspect all roadside vegetated slopes over a course of 5 years. After approval of the program by the SWRCB, a plan to inspect District slopes will be submitted to the RWQCB at a mutually agreeable date.

Training and Public Outreach

Training will be done as outlined in the SWMP

- (1) Significant road maintenance activities include projects involving grade changes, additional hydraulic capacity, direct or likely discharges to surface waters, increases in impervious surface area, or other activities identified or agreed to between RWQCB and Department staff.
- (2) Criteria

SWPPP = Greater than 5 acres of land disturbance (1 acre after March 2003)

303d = 303 (d)listed 401 = 401Cert.

SEP = Supplemental Environmental Project Retro = Storm Water Retrofit Project (SWMP 4.4.2)

LT = Lahontal RWQCB specific requirements for the Lake Tahoe Hydrologic Unit

HR = High Risk Area Present

RB = RWQCB designated projects posing a threat to water quality

SDRWQCB RWP

SECTION FIVE

TABLE 5-3: GENERAL MANAGEMENT PRACTICES

| Monitoring Activities | | | | | | | | | | |
|--|---|--|--|--|--|--|--|--|--|--|
| Monitoring activities will be conducted in accordance with the | e statewide program described in the Storm Water Monitoring Plan FY 01/02. | | | | | | | | | |
| LOCATION | 3 YR SW ACTION PLAN SUPPORTING STUDY | | | | | | | | | |
| San Diego 15 S | Acceleration/Deceleration Study | | | | | | | | | |
| San Diego 805 S | Acceleration/Deceleration Study | | | | | | | | | |
| San Diego 805 N | Acceleration/Deceleration Study | | | | | | | | | |
| San Diego 8 W PM 14.3 | Highway Runoff Characterization Study | | | | | | | | | |
| San Diego 5 N San Onofre | Acceleration/Deceleration Study | | | | | | | | | |
| San Diego 75 Coronado Bridge Toll Plaza | Toll Plaza and Weight station Characterization | | | | | | | | | |
| San Diego 5 San Onofre Truck Inspection | Toll Plaza and Weight station Characterization | | | | | | | | | |
| San Diego 15 S Via Rancho Parkway | Acceleration/Deceleration Study | | | | | | | | | |
| San Diego 5 Lomas Santa Fe | Acceleration/Deceleration Study | | | | | | | | | |
| Construction Compliance Monitoring Program | | | | | | | | | | |
| Construction activities are inspected through the Construction | on Compliance Monitoring Program. Monitoring results are provided in the annual | | | | | | | | | |
| report. | | | | | | | | | | |
| Training and Public Outreach | | | | | | | | | | |
| Training will be done as outlined in the SWMP | | | | | | | | | | |
| Municipal Coordination | | | | | | | | | | |
| | TO BY MOVED BY MICE STATE BY TO MAKE WITH | | | | | | | | | |

Attend San Diego MS4 Co-Permittee Meetings, participate in Project Clean Water Workgroups.

SDRWQCB RWP 5-9

REGIONAL WATER QUALITY CONTROL BOARD

REGION

CALTRANS DISTRICT

12

STORM WATER MANAGEMENT PROGRAM REGIONAL WORK PLAN FOR FISCAL YEAR 2002/2003

REGION 9

SAN DIEGO REGIONAL WATER QUALITY CONTROL BOARD CTSW-RT-01-075



California Department of Transportation

District 12 3337 Michelson Drive, Suite 380 Irvine, CA 92612-8894

April 1, 2002

CERTIFICATION REGIONAL WORK PLAN

California Regional Water Quality Control Board San Diego Region 9 Fiscal Year 2002/2003 April 1, 2002

CALIFORNIA DEPARTMENT OF TRANSPORTATION DISTRICT 12

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is true, accurate, and complete to the best of my knowledge and belief. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment of knowing violations. [40 CFR 122.22(d)]

FOR Cindy Quon District Director

| Tabl | e of (| Contents | Regional Work Plans |
|--------------------------|--------------------|---|---------------------|
| SECT | ION 1 | INTRODUCTION | 1-1 |
| SECT | ION 2 | DISTRICT 12 PERSONNEL AND RESPONSIBILITI | ES 2-1 |
| SECT | ION 3 | DISTRICT FACILITIES AND WATER BODIES | 3-1 |
| SECT | ION 4 | HIGH RISK AREAS | 4-1 |
| SECT | ION 5 | IMPLEMENTATION ACTIVITIES | 5-1 |
| m | | LIST OF TABLES | |
| Table 2-1 2-2 3-1 | Signat | ct 12 Storm Water Personnel and Responsibilities cory Authority for Key Documents ct 12 Facilities | 2-1 2-1 3-1 |
| 4-1 5-1 5-2 5-3 | Districi Antici | Risk Areas et 12 Anticipated Project Development/Construction Sc pated Maintenance Activities and Other Management l al Management Practices | |
| | | LIST OF FIGURES | |

2-2

3-2

2-1

3-1

District 12 Organizational Chart District 12 Map of Roadways and Water Bodies

1.0 INTRODUCTION

The purpose of the Regional Work Plans (RWPs) is to describe how the Department Districts will specifically implement the Statewide Storm Water Management Program (SWMP) within the jurisdiction of each Regional Water Quality Control Board during Fiscal Year 2002-2003 as required by the Caltrans Statewide Storm Water NPDES Permit – Order No. 99-06-DWQ (Permit). Implementation activities will be conducted in accordance with the procedures presented in the SWMP. The RWP indicates how District storm water management practices will be modified to improve water quality protection based on evaluation of the previous studies and management activities.

The RWP provides region-specific information on District 12 facilities, water bodies, and Best Management Practices (BMPs), and monitoring programs according to the following sections:

- Section 1 Introduction;
- Section 2 Personnel and Responsibilities;
- Section 3 District Facilities and Water Bodies;
- Section 4 High Risk Areas; and
- Section 5 Implementation Activities.

2.0 DISTRICT 12 PERSONNEL AND RESPONSIBILITIES

Portions of District 12 fall within the jurisdiction of the San Diego Regional Water Quality Control Board, Region 9 (coverage area). Organization chart for District 12 is included in Figure 2-1. Staff responsible for implementing the SWMP within the San Diego RWQCB jurisdiction are listed in Table 2-1.


TABLE 2-1: DISTRICT 12 STORM WATER PERSONNEL AND RESPONSIBILITIES

| Staff | Title | Phone Number | E-Mail Address | Responsibilities |
|----------------|----------------------------------|------------------|--------------------|--|
| Grace Piña- | District 12, NPDES | (949) 724-2189 | Grace_pina- | Primary contact for all |
| Garrett | Storm Water | | garrett@dot.ca.gov | storm water issues. |
| | Coordinator | | | Oversees all NPDES office |
| | | | | employees within the |
| | | | | District. |
| Hector Salas | Environmental | (949) 724-2625 | Hector Salas@dot.c | Under the Direction of the |
| | Specialist | | <u>a.gov</u> | District Storm Water |
| | (NPDES Unit) | | | Coordinator, the |
| | | | | Environmental Specialist |
| | | | | ensures permit compliance |
| | | | | from all functional units. |
| | | | | Contacts and submits all |
| | | | | information to RWQCB |
| | | | | (NOC, NCC, Non- |
| | | (2.42) = 2.4.2.4 | | compliance) |
| Behrooz | Construction Storm | (949) 724-2188 | Behrooz pirzadeh@ | Review and Approve |
| Pirzadeh | Water Coordinator | | dot.ca.gov | SWPPP/ WPCP |
| | | | | Documents. Liaison |
| | | | | between field Construction |
| | | (0.40) 440 | | and NPDES Unit |
| Carol Lonebear | | (949) 440-4466 | Carol Lonebear@do | Liaison between |
| | Water Coordinator | | t.ca.gov | Maintenance field crews |
| | | | | and Storm Water Unit. |
| | | | | Inspects Maintenance |
| | | | | facilities and provides |
| | | | | training to Maintenance |
| Leslie | En incompanial | (040) 704 0400 | Total Mondon des | field personnel. |
| Manderscheid | Environmental | (949) 724-2122 | Leslie Manderschei | Environmental Liaison to the NPDES Unit. Reviews |
| ivianuerscheid | Planning Storm Water Coordinator | | d@dot.ca.gov | |
| | Coordinator | | | projects in the planning and environmental |
| | | | | |
| Daniel Hing | Dight of May | (040) 724 2445 | Daniel Hina@datas | document Conducts Airspace Lease |
| Daniel Hing | Right of Way | (949) 724-2145 | Daniel Hing@dot.ca | |
| | Representative | | <u>.gov</u> | Inspections for Water |
| | | | <u> </u> | Quality |

In compliance with Permit Section M. 10. b, the following positions listed in Table 2-2 are authorized to sign the documents, reports and other information submitted by the District to either the State Water Resources Control Board or the Regional Water Quality Control Board(s).

TABLE 2-2: SIGNATORY AUTHORITY FOR KEY DOCUMENTS

| Positions | Documents Authorized for Signature |
|----------------------|--|
| Design Branch Chiefs | Notification of Construction (NOC) |
| Resident Engineers | Notice of Completion of Construction (NCC), SWPPP Approval |
| Chief, NPDES Unit | Transmittals to RWQCB |
| | Discharge or Threat of Discharge Notification |
| | Notice of Non-Compliance Notifications |
| | |
| Maintenance SWC | Facility Pollution Prevention Plan (FPPP) |



3.0 DISTRICT FACILITIES AND WATER BODIES

This section identifies the Department facilities and water bodies within each District and Regional Board jurisdiction. A list of District 12 facilities, excluding roadways, is presented in Table 3-1. Maps showing the District 12 boundaries within the San Diego RWQCB, and major roads and highways are presented in Figure 3-1

TABLE 3-1: DISTRICT 12 FACILITIES

| CO | Route | PM | Name | Comments | | | | | | | | | |
|--------|---|--------------|---------------------|--|--|--|--|--|--|--|--|--|--|
| | | Maintenance | e Stations | | | | | | | | | | |
| Orange | 5 | 8.8 | San Juan Capistrano | Highway Maintenance | | | | | | | | | |
| Orange | 5 | 13.7 | Forbes | Landscape Maintenance | | | | | | | | | |
| Orange | 5 | 8.8 | San Juan Capistrano | Landscape Maintenance | | | | | | | | | |
| | Commercial Vehicle Enforcement Facilities | | | | | | | | | | | | |
| NONE | | | | | | | | | | | | | |
| | | Park and Rid | e Facilities | | | | | | | | | | |
| Orange | 5 | 10.9 | Junipero Serra | SE Corner of Junipero Serra & I-5 in San Juan Capistrano | | | | | | | | | |
| | Toll Road and Bridge Plazas | | | | | | | | | | | | |
| Orange | 73 | 18.7 | Catalina | Toll Plaza | | | | | | | | | |

Lists and maps of the Department of Water Resource Hydrologic Units located within the coverage area are presented in Appendix A of the SWMP. Specific information on the Department facilities and water bodies may also be found at the following website: http://stormwater.water-programs.com

District 12 State of California Department of Transportation Orange County



LEGEND











4.0 HIGH RISK AREAS

A list of high risk areas within District 12 is presented in Table 4-1. High risk areas are defined in the Section E.2 of the Permit to include areas such as locations where spills from District 12 owned right-of-ways, activities, or facilities can discharge directly to municipal or domestic water supply reservoirs or ground water percolation facilities. Additional sites may be added to the high-risk list based on discussion between the Regional Water Quality Control Board (RWQCB) and Caltrans. The Permit requires consideration of appropriate spill containment and spill prevention control measures for these areas.

In order to generate the list of high-risk municipal and domestic water supply reservoirs and ground water percolation facilities, District 12 first contacted known public and private water supply providers. From the information received, District 12 determined which facilities were susceptible to a direct spill from the Department activity or facility. This determination was based on proximity between the water body and Caltrans facility, use characteristics of the facilities, and the probable spill response time.

The Department will consider and implement spill containment and prevention control measures in accordance with the processes contained in the SWMP including Section 3 for BMP identification and implementation, Section 4.4.1 for new construction projects or Section 4.4.2 for retrofit projects that are within these areas.

TABLE 4-1: HIGH RISK AREAS

| Road Segment/ Facility | County | High Risk Area | Description | Comments |
|---------------------------|--------|----------------|-------------|----------|
| None | | | | |
| | | | | |

5.0 IMPLEMENTATION ACTIVITIES

This section presents specific project work planned for the year and indicates BMP implementation improvements. The anticipated schedule of construction and maintenance activities is subject to change. The Department will discuss with the RWQCBs new projects meeting the criteria listed below when ground disturbance takes place or when significant maintenance activities are initiated during the year. These projects are updates to the RWP provided in April.

Table 5-1 includes a list of construction projects that meet one or more of the following criteria:

- The project involves greater than 5 acres (1 acre after 2003) of land disturbance, designated as "SWPPP";
- The project affects a 303(d) listed water body within the project limits, designated as "303d";
- The project requires a 401 Water Quality Certification or Waiver, designated as "401";
- The project is a Supplemental Environmental Project (water quality project negotiated by the RWQCB and Caltrans) designated as "SEP";
- The project is a storm water retrofit project (SWMP Section 4.4.2), designated as "Retro";
- The project limits are with a "High Risk Area," designated as "HR"; and
- The project is designated by a RWQCB as posing a potential threat to water quality, designated as "RB."

The information presented in Table 5-1 is intended to facilitate early RWQCB staff input in the project planning phase in accordance with Section L.8 of the Permit and Section 4.4 of the SWMP. The goal is to resolve water quality issues that may affect project funding, permitting, and scheduling. In addition, projects that require RWQCB review and approval of project SWPPPs/WPCPs in accordance with Sections H.8 and L.8 of the Permit are also covered in Table 5-1.

Table 5-2 presents a list of anticipated significant maintenance projects that have the potential to impact water quality and provides early notification of such activities. It also includes region-specific issues and BMP actions/modifications based on program evaluations discussed in current and/or past Annual Report(s).

Table 5-3 summarizes various program management activities that are part of the storm water pollution prevention program.

TABLE 5-1: DISTRICT 12 ANTICIPATED PROJECT DEVELOPMENT/CONSTRUCTION SCHEDULE

| | | | | | | | | | | • | Project Dev | elopment | Constru | ction Period |
|-----|--------------------|-------|-----|-------|------|--|---------------------------|--------------------|--------------------------------|---|--|--|---------------|--------------------|
| No. | SWMP Category** | EA# | Co. | Route | PM | Description | Water Bodies Affected | Criteria* | Land Disturbance Acreage | Project Scoping (PID) Preliminary Env. Evaluation | Project Dev. (PA&ED) - Draft EIS/EIR | Final Design (PS&E) - Permits & Mitigation | Start Date | Completion Date |
| 1 | D | 0E110 | ORA | 000 | 10.2 | TO CONSTRUCT FIBER OPTIC &HUB STATION | | | | 12/10/99** | 6/1/00 | 6/1/01 | 12/1/01 | 12/1/02 |
| 2 | С | 0008E | ORA | 073 | 05.4 | WIDEN FREEWAY AND HOV LANES | ALISO CREEK | SWPPP | | 11/20/89 | 12/1/96 | 3/1/01 | 11/1/01 | 3/1/03 |
| 3 | С | 09790 | ORA | 005 | 00.0 | UPGRADE APPROACH RAIL- BRIDGE RAIL | SAN MATEO CREEK | SWPPP | | 11/4/99 | 2/1/01 | | 1/1/03 | 1/1/04 |
| 4 | С | 0A390 | ORA | 005 | 7.4 | REALIGN CAMINO CAPIST/STONEHILL | SAN JUAN CREEK | WPCP?? / 303(d) | | 1/5/00 | 1/1/01 | | 1/1/03 | 1/1/04 |
| 5 | С | 0E030 | ORA | 005 | 06.8 | DOWEL RETROFIT TRUCK LANES BOTH DIR | SAN JUAN CREEK | ?? / 303(d) | | 12/1/99 | 1/1/01 | | 1/1/04 | 6/1/05 |
| 6 | С | 0E020 | ORA | 005 | 14.5 | DOWEL RETROFIT TRUCK LANES BOTH DIR | OSO CREEK | | | 8/1/01 | 8/1/01 | | 2/1/04 | 5/1/05 |
| 7 | С | 0C860 | ORA | 005 | 04.4 | HWY PLANTING RESTORATION | PACIFIC OCEAN | SWPPP | | 10/1/01 | 12/1/01 | | 7/1/05 | 12/1/05 |
| 8 | С | 0C880 | ORA | 005 | 01.6 | HIGHWAY PLANTING RESTORATION | PACIFIC OCEAN | SWPPP | | 10/1/01 | 12/1/01 | | 7/1/05 | 12/1/05 |
| 9 | С | 0E930 | ORA | 005 | 13.7 | HIGHWAY PLANTING RESTORATION | OSO CREEK | SWPPP | | 10/1/00 | 3/1/01 | | 10/1/05 | 4/1/06 |
| 10 | С | 0A980 | ORA | 073 | 9.6 | LANDSCAPING ENHANCEMENT | LOS TRANCOS CREEK | SWPPP | | 1/1/01 | 7/1/01 | | 1/1/06 | 2/1/07 |
| 11 | С | 0E170 | ORA | 005 | 01.2 | TO IDENTIFY & SCREEN CONGESTION | SAN MATEO CREEK | | | 12/1/99 | 1/1/00 | | | |
| 12 | В | 10287 | ORA | 005 | 03.7 | CONST INTERCHANGE | PACIFIC OCEAN | SWPPP | | 10/31/89 | 8/1/97 | 12/20/99 | 6/1/01 | 12/1/02 |
| 13 | В | 0A910 | ORA | 241 | 19 | ADDITION OF UP TO TWO LANES IN EACH | TRABUCO CREEK | SWPPP | | 4/1/00 | 7/1/00 | | 8/1/02 | 3/1/03 |
| 14 | В | 09740 | ORA | 133 | 00.0 | DRAINAGE IMPROVEMENTS | PACIFIC OCEAN | SWPPP | | 1/13/00 | 10/1/00 | | 9/1/02 | 9/1/03 |
| 15 | В | 0A920 | ORA | 241 | 18.5 | ADDITION OF UP TO TWO LANES IN EACH | TRABUCO CREEK | SWPPP | | 4/1/00 | 7/1/00 | | 10/1/02 | 7/1/03 |
| 16 | В | 0C550 | ORA | 133 | 0 | PAVEMENT REHABILITATION | PACIFIC OCEAN | SWPPP | | 6/1/01 | 6/1/01 | | 1/1/03 | 12/1/03 |
| 17 | В | 1072U | ORA | 133 | 04.1 | WIDEN AND REALIGN RDWY | BOMMER CANYON CREEK | SWPPP | | 12/22/93 | 7/1/01 | | 1/1/03 | 1/1/05 |
| 18 | В | 0A900 | ORA | 241 | 24.7 | ADDITION OF UP TO TWO LANES IN EACH | ALISO CREEK | SWPPP | | 12/1/99 | 7/1/00 | | 1/1/03 | 5/1/06 |

TABLE 5-1: DISTRICT 12 ANTICIPATED PROJECT DEVELOPMENT/CONSTRUCTION SCHEDULE

| | | | | | | | | | | | Project Deve Schedule | elopment | Constru | ction Period |
|-----|------------|-------|-----|-------|------|--|---------------------------|-------------------------------|---------------------|---|---------------------------------------|--|---------|--------------|
| | SWMP | | | | | | Water Bodies | | Land Disturbance | Project Scoping (PID) Preliminary Env. | Project Dev. (PA&ED) - Draft | Final Design (PS&E) - Permits & | Start | Completion |
| No. | Category** | EA# | Co. | Route | PM | Description | Affected | Criteria* | Acreage | Evaluation | EIS/EIR | Mitigation | Date | Date |
| 19 | В | 0C050 | ORA | 133 | 4.1 | INSTALL SOFT BARRIER | BOMMER CANYON CREEK | SWPPP | | 7/1/01 | 1/1/02 | | 3/1/03 | 12/1/03 |
| 20 | В | 0C380 | ORA | 001 | 12.1 | CRYSTAL COVE STORM WATER QUALITY | PACIFIC OCEAN | SWPPP | | 3/1/01 | 6/1/01 | | 3/1/03 | 10/1/03 |
| 21 | В | 0A220 | ORA | 005 | 12 | SUPERELEVATION MODIFICATION | OSO CREEK | SWPPP | | 5/8/01 | 1/1/02 | | 3/1/03 | 11/1/03 |
| 22 | В | 0C370 | ORA | 001 | 3.3 | PCH WIDENING/ADDITION OF CLASS 1 | PACIFIC OCEAN | | | 1/2/01 | 12/1/01 | | 4/1/03 | 10/1/03 |
| 23 | В | 0E700 | ORA | 001 | 01.0 | WIDENING OF THE BRIDGE SIDEWALK AT | SAN JUAN CREEK | SWPPP/ 303(d) | | 8/1/01 | 3/1/02 | | 4/1/03 | 3/1/04 |
| 24 | В | 0C690 | ORA | 001 | 02.4 | CONSTRUCT RAISED- LANDSCAPED MEDIAN | PACIFIC OCEAN | SWPPP | | 2/1/02 | 8/1/02 | | 5/1/03 | 4/1/04 |
| 25 | В | 0A400 | ORA | 005 | 7.4 | CONSTRUCTION OF OUTER SEPARATION | SAN JUAN CREEK | SWPPP/ 303(d) | | 8/18/00 | 7/1/01 | | 5/1/03 | 5/1/04 |
| 26 | В | 0A040 | ORA | 133 | 3.4 | ROADWAY WIDENING | BOMMER CANYON CREEK | SWPPP | | 12/22/99 | 7/1/02 | | 7/1/03 | 6/1/05 |
| 27 | В | 0C670 | ORA | 005 | 1.7 | REHAB AC PAVEMENT IN BOTH DIRECTION | SAN MATEO CREEK | SWPPP | | 10/1/01 | 10/1/01 | | 8/1/03 | 7/1/04 |
| 28 | В | 0A260 | ORA | 005 | 8.9 | SCOUR MITIGATION | SAN JUAN CREEK | SWPPP? | | 5/1/00 | 5/1/01 | | 9/1/03 | 9/1/04 |
| 29 | В | 0C070 | ORA | 001 | 0.3 | UPGRADE BRIDGE RAIL & INSTALL | SAN JUAN CREEK | SWPPP/ 303(d) | | 4/1/01 | 12/1/01 | | 11/1/03 | 5/1/04 |
| 30 | В | 0E070 | ORA | 005 | 15.1 | WIDEN NB OSO PKWY LOOP ON RAMP SB | OSO CREEK | SWPPP | | 9/1/01 | 10/1/02 | | 2/1/05 | 4/1/07 |
| 31 | В | 0E570 | ORA | 005 | 08.4 | RECONSTRUCT DFF RAMP ADD 2 LEFT | SAN JUAN CREEK | SWPPP/ WPCP ?? / 303(d) | | 8/1/01 | 8/1/03 | | 2/1/05 | 3/1/06 |
| 32 | В | 04320 | ORA | 074 | 13.3 | WIDEN RDWY | SAN JUAN CREEK | SWPPP/ 303(d) | | 12/5/97 | 1/1/03 | | 6/1/05 | 10/1/06 |
| 33 | В | 08430 | ORA | 005 | 03.4 | UPGRADE PLANTING & IRRIGATION | PACIFIC OCEAN | SWPPP | | 11/6/97 | 4/1/04 | | 9/1/05 | 9/1/09 |
| 34 | В | 08450 | ORA | 005 | 00.1 | UPGR PLTG & IRR ADD SAFETY FEATURES | PACIFIC OCEAN | SWPPP | | 10/6/97 | 4/1/04 | | 9/1/05 | 9/1/09 |
| 35 | В | 0A940 | ORA | 073 | 9.6 | ADDITION OF UP TO TWO LANES IN EACH | LOS TRANCOS CREEK | SWPPP | | 12/1/03 | 7/1/04 | | 12/1/05 | 12/1/12 |

SECTION FIVE

TABLE 5-1: DISTRICT 12 ANTICIPATED PROJECT DEVELOPMENT/CONSTRUCTION SCHEDULE

| | | | | | | | | | | Anticipated | Project Dev | elopment | Constru | ction Period |
|-----|--------------------|-------|-----|-------|------|--|--------------------------|------------------|--------------------------------|---|--|--|---------------|--------------------|
| No. | SWMP Category** | EA# | Co. | Route | PM | Description | Water Bodies Affected | Criteria* | Land Disturbance Acreage | Project Scoping (PID) Preliminary Env. Evaluation | Project Dev. (PA&ED) - Draft EIS/EIR | Final Design (PS&E) - Permits & Mitigation | Start Date | Completion Date |
| 36 | В | 09800 | ORA | 005 | 18.1 | RELOCATE S/B I-5 ON & OFF RAMPS | ALISO CREEK | SWPPP | | 8/1/01 | 5/1/03 | | 1/1/06 | 7/1/06 |
| 37 | В | 0A070 | ORA | 005 | 16.5 | RECONSTRUCT UNDERCROSSING AT LA PAZ | ALISO CREEK | SWPPP | | 9/1/01 | 7/1/04 | | 2/1/06 | 2/1/08 |
| 38 | В | 0E620 | ORA | 005 | 16.8 | EXTEND 1 AUXILIARY LANE FROM ALICIA | ALISO CREEK | SWPPP | | 7/1/01 | 7/1/04 | | 2/1/06 | 2/1/07 |
| 39 | В | 0E310 | ORA | 074 | 00.0 | RECONSTRUCT IC AT SR-74 | SAN JUAN CREEK | SWPPP/ 303(d) | | 6/1/01 | 12/1/03 | | 3/1/06 | 5/1/09 |
| 40 | В | 08690 | ORA | 074 | 01.3 | WIDEN EXIST 2 LANE RDWY TO 4 LANES | SAN JUAN CREEK | SWPPP/ 303(d) | | 12/15/97 | 10/1/02 | | 10/1/06 | 1/1/08 |
| 41 | В | 0A950 | ORA | 073 | 11.5 | CALTRANS MAINTENANCE FACILITY | BUCK GULLY | SWPPP | | 4/1/00 | 7/1/00 | | 12/1/09 | 4/1/10 |
| 42 | В | 08820 | ORA | 074 | 00.0 | AERIAL SURVEY AND REALIGN HIGHWAY | SAN JUAN CREEK | SWPPP/ 303(d) | | 6/1/99 | | | | |
| 43 | Α | 0C520 | ORA | 241 | 18.1 | CONSTRUCT BRIDGE | TRABUCO CREEK | SWPPP | | 5/1/01 | 6/1/01 | | 9/1/02 | 10/1/02 |
| 44 | Α | 0C820 | ORA | 241 | 05.5 | ENCROACHMENT PERMIT TO REGRADE SLOPE | OSO CREEK | SWPPP | | 4/1/02 | 4/1/02 | | 8/1/03 | 2/1/04 |
| 45 | А | 0A890 | ORA | 241 | 24.7 | ADDITION OF TWO LANES IN EACH DIREC | ALISO CREEK | SWPPP | | 2/1/03 | 7/1/03 | | 5/1/04 | 12/1/08 |
| 46 | А | 09520 | ORA | 005 | 14.6 | REPAIR OSO CHANL.(PAR KJK CT12 011) | OSO CREEK | SWPPP | | | | | | |

* Criteria

SWPPP = Greater than 5 acres of land disturbance

303d = 303 (d) listed water body within project limits and affected by project

401 = 401 Certification/Waiver required
SEP = Supplemental Environmental Project
Retro = Storm Water Retrofit Project (SWMP 4.4.2)
HR = Project limits within High Risk Area

RB = RWQCB designated project as a potential threat to water quality

Note: Actual dates are provided in Italics

** SWMP Category is defined in SWMP Section 4.4.1, Table 4-3,

- (A) Beginning of Project Development Process prior to approval of the PSR
- (B) PSR approved but Environmental Documents are not final
- (C) Environmental Documents are final
- (D) Environmental documents final, design complete and project in the construction phase of project delivery

TABLE 5-2: ANTICIPATED MAINTENANCE ACTIVITIES AND OTHER MANAGEMENT PRACTICES

| Significant Road Maintenance Activities (1) | | | | | | | | | | |
|---|-------|----|-------------|--------------------------|-------------|------------|--------------------|--|--|--|
| County | Route | РМ | Description | Water Bodies Affected | Criteria(2) | Start Date | Completion Date | | | |
| NONE | | | | | | | | | | |
| | | | | | | | | | | |

Maintenance Facility and Activity Inspections

District 12 Maintenance facilities are inspected weekly by the Maintenance facility supervisor. Per the requirements of the SWMP, the District 12 Maintenance Storm Water Coordinator will review at least 20% of District 12's facilities each year (Section 5.6).

Maintenance Facility BMP Improvements

NONE

Maintenance BMP Actions/Modifications

NONE

Vegetation Management and Vegetated Slope Management

Vegetation Control Plan- The District 12 Vegetation Control Plan (VCP) for FY 2002/03 is under development. The VCP goal is to minimize the discharge of the chemicals to receiving waters by reducing chemical use for vegetation control. The VCP includes the following major items:

- Type of chemical to be applied and form (dry or liquid)
- Application locations, lengths, widths, total area, rates, frequency, total amount
- Reason for application
- Mowing program

District 12 will provide the VCP for FY 02/03 to the San Diego RWQCB by May 15, 2002.

Vegetated Slope Evaluation- The Department's Maintenance Inspection and Slope Stabilization Team (MISST) created a Preliminary Slope Inspection Form, further discussed in Annual Report Section 5.2.3, that will be used to inspect all roadside vegetated slopes over the course of 5 years. After approval of the program by the SWRCB, a plan to inspect District slopes will be submitted to the RWQCB at a mutually agreeable date.

| Route/PM | County | Inspection Remediation Ac Schedule Planned | |
|----------|--------|--|--|
| | | | |

SECTION FIVE Regional Work Plans

(1) Significant road maintenance activities includes projects involving grade changes, additional hydraulic capacity, direct discharges to surface waters, increases in impervious surface area, or other activities identified or agreed to between RWQCB and Caltrans staff.

(2) Criteria

SWPPP = Greater than 5 acres of land disturbance

303d = 303 (d) listed water body with project limits and affected by project

401 = 401 Certification/Waiver required
 SEP = Supplemental Environmental Project
 Retro = Storm Water Retrofit Project (SWMP 4.4.2)

LT = Lahontan RWQCB specific requirements for the Lake Tahoe Hydrologic Unit

HR = Project limits within High Risk Area

RB = RWQCB designated projects as a potential threat to water quality

SECTION FIVE

TABLE 5-3: GENERAL MANAGEMENT PRACTICES

Monitoring Activities

Monitoring activities will be conducted in accordance with the statewide program described in the Storm Water Monitoring Plan FY 001/002. Site Specific Monitoring and Reporting for the Compost Storm Water Filters on SR-73 will be conducted in accordance with the San Diego RWQCB Cease and Desist Order No. 2001-198. District 12 has submitted a Water Quality Monitoring Plan on October 31, 2001, which identifies the 3 sites selected for water quality monitoring. In accordance with the CDO, monitoring at the selected sites will continue until the CDO is rescinded.

Construction Compliance Program

Construction activities are inspected through the Construction Compliance Monitoring Program. Monitoring results are provided in the annual report.

The District Construction Storm Water Coordinator prior to start of construction will review the Storm Water Pollution Prevention Plans (SWPPPs) for Caltrans Construction projects.

Notification of Construction (NOC) forms will be completed and submitted to the Santa Ana RWQCB 30 days prior to the start of construction. Notice of Completion of Construction (NCC) forms will be submitted when a construction project is complete. NCC forms will be submitted when the soil stabilization of the project meets the requirements of the General Construction Permit.

Training and Public Outreach

Caltrans District 12 will be involved in the Annual Children's Water Education Festival hosted by the Orange County Water District and Disneyland. Members of the District 12 Storm Water Program address the various issues in storm water pollution prevention to over 5,000 elementary school children.

The Division of Planning and Design currently reference the Project Planning and Design Guide (PPDG) (May 2000) to include water quality measures in the project planning and design process. A revision of the PPDG is currently being drafted. When presented with a final revision of the PPDG, Caltrans will provide training for its employees in the revisions of the PPDG.

Maintenance staff guidance materials provide direction, guidance, policies and procedures for all maintenance activities. The guidance materials used regularly in tailgate training of Maintenance staff as they begin an activity. First Responder Awareness training is consistently provided for all maintenance and shop personnel. This training emphasizes the 3-D approach- divert, dike, and dam- so that spills seldom approach highway drainage courses. Emergency response contractors are on call for cleanup around the clock according to the districts hazardous material spill contingency plan

Municipal Coordination

The County of Orange, the Orange County Flood Control, and 24 of the 33 Orange County cities are co-permittees on a municipal NPDES Permit with the San Diego RWQCB. Newly incorporated cities will be added as Orange County co-permittees. The County of Orange and its co-permittees host Technical Advisory Committee (TAC) meetings as well as co-permittee meetings. The District 12 Storm Water Coordinator and the Storm Water Program Manger will attend Orange County TAC meetings and maintain a continuous exchange of information.

Regional Work Plans