

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

April 24, 2003

02-Sha-5-R6.1/R9.5
02-396604

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SHASTA COUNTY IN AND NEAR ANDERSON FROM ROUTE 273 SEPARATION TO TORMY DRAIN BRIDGE.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on May 6, 2003.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions and the Proposal and Contract.

Project Plan Sheets 10 and 11 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 9, "DESCRIPTION OF BRIDGE WORK," the first paragraph is revised to read as follows:

"The bridge work to be done consists, in general, of replacing approach slabs and joint seals and treating approach pavement at the following structures as shown on the plans."

In the Special Provisions, Section 10-1.185, "CLEAN EXPANSION JOINTS," is added as attached.

In the Proposal and Contract, the Engineer's Estimate Items 11 and 12 are revised, Item 16 and 17 are added and Item 15 is deleted as attached.

To Proposal and Contract book holders:

Replace the entire Engineer's Estimate in the Proposal with the attached revised Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 1
Page 2
April 24, 2003

02-Sha-5-R6.1/R9.5
02-396604

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY M C GUINNESS FOR:

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

10-1.185 CLEAN EXPANSION JOINTS

All deck joints shown on the plans to be cleaned, shall be cleaned as specified herein.

Cleaning shall include removal of all existing seal material, dirt, debris, damaged waterstop, and joint filler, and shall be accomplished by methods which do not damage existing sound concrete surfaces.

Joint size shall be verified after the joint has been cleaned.

The Contractor shall take necessary precautions to ensure that material removed from expansion joints does not fall onto public traffic, railroad property, private property, or into the waterway beneath the bridges. The Contractor shall submit for the Engineer's approval, details for preventing material, equipment, or debris from falling onto traffic or railroad property.

Joints shall be cleaned down to the hinge seat or bearing seat, unless otherwise directed by the Engineer.

Repairing existing joint damage will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. The cost of repairing damage caused by the Contractor's operations shall be borne by the Contractor.

Materials removed from the expansion joint, except for surface dust, shall be recovered and disposed of away from the site in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Cleaning expansion joints will be measured by the meter for the length of the deck joint as shown on the plans.

The contract price paid per meter for clean expansion joint shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in cleaning expansion joints, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

ENGINEER'S ESTIMATE**02-396604**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
2	074020	WATER POLLUTION CONTROL	LS	LUMP SUM	LUMP SUM	
3	074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	1		
4	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
5	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
6	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	3		
7	153235	CLEAN BRIDGE DECK	M2	1343		
8	260210	AGGREGATE BASE (APPROACH SLAB)	M3	39		
9	510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	378		
10	510800	PAVING NOTCH EXTENSION	M3	11		
11 (S)	519117	JOINT SEAL (MR 30 MM)	M	160		
12 (S)	519120	JOINT SEAL (MR 15 MM)	M	36		
13 (F)	540102	TREAT BRIDGE DECK	M2	1343		
14	540109	FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	L	745		
15	BLANK					
16	511118	CLEAN EXPANSION JOINT	M	54		
17	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____