

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY (916) 227-8454



*Flex your power!
Be energy efficient!*

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

September 8, 2006

04-Sol-505-0.0/17.0
04-0C8304

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SOLANO COUNTY IN VACAVILLE FROM 505/80 SEPARATION TO YOLO COUNTY LINE.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on September 27, 2006.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

Project Plan Sheets 1 and 23 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.14, "MAINTAINING TRAFFIC", the lane closure chart table, "Chart No. 20," is added as attached.

In the Special Provisions, Section 10-1.22, "ASPHALT CONCRETE", the following paragraphs are added after the last paragraph:

"The area to which paint binder has been applied shall be closed to public traffic. Care shall be taken to avoid tracking binder material onto existing pavement surfaces beyond the limits of construction.

A vertical longitudinal joint of more than 45 mm will not be allowed at any time between adjacent lanes open to public traffic.

The Contractor shall schedule paving operations so that each layer of asphalt concrete is placed on contiguous lanes of the traveled way during each work shift. At the end of each work shift, the distance between the ends of the layers of asphalt concrete on adjacent lanes shall not be greater than 3 m or less than 1.5 m. Additional asphalt concrete shall be placed along the transverse edge at the end of each lane and along the exposed longitudinal edges between adjacent lanes, hand raked, and compacted to form temporary conforms. Kraft paper, or other approved bond breaker, may be placed under the conform tapers to facilitate the removal of the taper when paving operations resume.

Shoulders or median borders adjacent to a lane being paved shall be surfaced prior to opening the lane to public traffic."

Addendum No. 3
Page 2
September 8, 2006

04-Sol-505-0.0/17.0
04-OC8304

In the Proposal and Contract, the Engineer's Estimate Items 16 and 22 are revised.

To Proposal and Contract book holders:

Replace the entire Engineer's Estimate in the Proposal with the attached revised Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO CONTRACTORS section of the Notice to Contractors and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it. A copy of this addendum is available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

Chart No. 20 Ramp Lane Requirements																									
Location: Eastbound- Route 80 – Connector Ramp to Route 505 (PM 28.00), Solano County																									
FROM HOUR TO HOUR	a.m.												p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1					1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1
Saturdays	1	1	1	1	1	1	1	1	1	1	1	1						1	1	1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1	1	1	1					1	1	1	1	1	1	1	1
Day before designated legal holiday																									
Designated legal holidays																									
Legend:																									
1	One Connector Ramp lane open in direction of travel																								
	No lane closure, shoulder closure or work that interferes with public traffic will be allowed																								
REMARKS:																									

(F=Sol-80- 28/0C8301/8.06/28.03/R)

ENGINEER'S ESTIMATE
04-0C8304

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
2	070018	TIME-RELATED OVERHEAD	WDAY	180		
3	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
4	074020	WATER POLLUTION CONTROL	LS	LUMP SUM	LUMP SUM	
5	074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	10		
6	074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	1		
7	074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	6		
8 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
9 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
10 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	4		
11	150722	REMOVE PAVEMENT MARKER	EA	14 100		
12	150771	REMOVE ASPHALT CONCRETE DIKE	M	6490		
13	150846	REMOVE CONCRETE PAVEMENT	M3	180		
14	151625	RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	M	1180		
15	152439	ADJUST FRAME AND GRATE TO GRADE	EA	6		
16	153154	COLD PLANE ASPHALT CONCRETE PAVEMENT (60 MM MAXIMUM)	M2	32 500		
17	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
18	198007	IMPORTED MATERIAL (SHOULDER BACKING)	M3	3850		
19	260210	AGGREGATE BASE (APPROACH SLAB)	M3	9		
20	390095	REPLACE ASPHALT CONCRETE SURFACING	M3	1710		

ENGINEER'S ESTIMATE**04-0C8304**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	390102	ASPHALT CONCRETE (TYPE A)	TONN	840		
22	390126	RUBBERIZED ASPHALT CONCRETE (TYPE G)	TONN	87 400		
23	394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	M	6490		
24	038168	SHOULDER RUMBLE STRIP	M	62 400		
25	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	470		
26	401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	M3	2210		
27	510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	82		
28	510800	PAVING NOTCH EXTENSION	M3	3		
29	519117	JOINT SEAL (MR 30 MM)	M	210		
30 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	110		
31 (S)	840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	71 300		
32 (S)	840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	1770		
33 (S)	840571	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	M	560		
34 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	8860		
35 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	5160		
36	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____